

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 106-61

LOCATION SW SE NE

SEC. 21 TWP. 11 RGE. 17 *W*

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease F.A. Bemis DIBKCC

Operator Phillips Pet Co Address Box 779 Great Bend, Kans

Field _____ County Ellis

Total Depth 3352 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 1070' circulated with cement - 7" at 3345' with 150
sax cement behind.

Filled with sand to 3330', set 5 sax cement with dump bailer,
pulled 2568' 7" - filled hole with mud to 300' (35 sax Gel) set
rock and 30 sax cement at 300' - mud to 49', set rock and 20 sax
cement to bottom cellar.

Edwin Petty

District Conservation Agent

Date 11-14-56

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING DIVISION
NOV 16 1956
11-16-56
FILE SEC. 21 T. 11 R. 17W
BOOK PAGE 106 DISTRICT CONSERVATION DIVISION
Wichita, Kansas