

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 122-36
LOCATION SE SE SE
SEC. 21 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease Bemis

Operator Cities Service Oil Address Box 553 Russell, Kans

Field _____ County Ellis

Total Depth 3482 Feet.

Plugging Contractor J. Shull

Plugging Contractor's License No. 8

Address _____
(Describe briefly the manner in which the well was plugged)

15" at 93' circulated with cement - 10" at 1120' circulated
with cement - 7" at 3390' with 350 sax cement behind - 4 1/2" at
3451' with 50 sax cement behind.

Filled with sand to 3350', set 5 sax cement - pulled 3040' 4 1/2" &
2340' 7" - filled hole with mud to 300', set rock and 25 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

Edon Lee
District Conservation Agent

Date 6-8-55

PLUGGING
FILE SEC 21 TWP 11 RGE 17
BOOK PAGE 122 LINE 36

VED
COMMISSION
JUN 14 1955
06.14-55
CONSERVATION DIVISION
Wichita, Kansas