

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 115-37

LOCATION NW NE NE

SEC. 21 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Bemis

Operator El Dorado Refg Co Address El Dorado, Kans

Field Bemis County Ellis

Total Depth 5344 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 98' circulated - 10" at 1042 circulated with cement.

7" at 3339' - Heavy mud to 2740' , ripped off 7" at 1060'.

filled hole with heavy mud to 250', set wood plug, rock bridge

and 25 sax cement, filled with heavy mud to 30', wood plug

and 20 sax cement to bottom cellar,

RECORDED

Edon Lee

District Conservation Agent

COMMISSIONER
KANSAS

Date 10-5-49

RWD
10-06-49

PLUGGING
FILE SEC 21 TWP 11 RGE 17
BOOK PAGE 113 LINE 37