

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 119-45
LOCATION SW SE SE
SEC. 21 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease _____ Bemis _____

Operator Cities Service Co Address Box 751 Great Bend, Kans

Field Bemis County Ellis

Total Depth 3412 Feet.

Plugging Contractor B & A pipe pulling Co

Plugging Contractor's License No. 17

Address _____

(Describe briefly the manner in which the well was plugged)

20" at 20" circulated with cement - 15" at 110' circulated with
cement - 10 3/4" at 1120' circulated with 475 sax cement - 7"
at 3389' with 340 sax cement behind.

Chat and sand to 3394', set 6 sax cement with dump bailer, pulled
2350' 7" casing, mud to 300', set rock and 25 sax cement, mud to
30', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC. 21 T. 11 R. 17W
BOOK PAGE 119 LINE 45

STAMP: 01-04-54
CONSERVATION DIVISION
Wichita, Kansas

Edmund Kelly
District Conservation Agent
Date 12-27-53