

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 68-45

LOCATION SW NE SE

SEC. 21 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 7 Lease \_\_\_\_\_ Bemis \_\_\_\_\_

Operator Cities Service Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3401 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 126' - circulated with cement - 10" at 1105'

circulated with cement - 7" at 3395', with 250 sax behind.

Mud to 2880', lost tools in hole 2857', set 5 sax cement with

dump bailer at 2857', pulled 2500' 7", filled hole with

heavy mud to 290', set rock bridge and 20 sax cement,

filled with mud to 35', set rock bridge and 10 sax

cement to bottom cellar

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1951

CONSERVATION DIVISION  
Wichita, Kansas

*John J. ...*  
District Conservation Agent

Date 5-11-51

PLUGGING  
FILE SEC 21 T 11 R 17  
BOOK PAGE 68 LINE 45