

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ormand Industries, Inc.
Complete Address 12011 San Vincente Blvd., Los Angeles, California 90049
Lease Name Bemis "D" Well No. 7
Location NE ^{NE} NE Sec. 21 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3421'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour Day 28th Month April Year 1973

The above well was plugged as follows:

Total Depth 3421" 10 3/4 csg set at 1039" cwc 600 sk.
7" csg set at 3412" cw 300 sk cmt.
Filled 7" csg W/sd (3400-3421) Dumped 6 sk cmt W/dump bailer. (3370-3400)
Cutoff and recovered 1509' of 7" csg.
Set 10 3/4 wood plug at 325' -rock & sand bridge (315-325)
Dumped 6 yds readymix cement from 315' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 5/2/73
INV. NO. 7313-W