

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 47-2

LOCATION NE SW SE

SEC. 21 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 11 Lease Bemis

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3378 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 90' circulated with cement-10 3/4" at 1097' circulated  
with 485 sax cement - 7" at 3368' with 270 sax cement behind  
Filled with chat to 3355' set 5 sax cement with dump baler,  
pulled 1350' 7", filled with mud to 300', set rock and 25  
sax cement, mud to 35', set rock and 10 sax cement to bottom  
cellar.

**PLUGGING**  
FILE SEC 21 T 11 R 17  
BOOK PAGE 47 LINE 2

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 14 1952  
10-14-52  
CONSERVATION DIVISION  
Wichita, Kansas

*John Lee*  
District Conservation Agent  
Date 10-11-52