

*BR*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 17-9

LOCATION SW SW SE

SEC. 21 TWP. 11 RGE. 17

Dry Hole            Abandoned Oil Well  Abandoned Gas Well           

I have this date completed supervision of plugging of:

Well No. 10 Lease            Bemis           

Operator Cities Service Co Address Great Bend, Kans

Field Bemis County Ellis

Total Depth ~~3414~~ 3454 Feet             
*PUB lic*

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address           

(Describe briefly the manner in which the well was plugged)

15" at 115' circulated with cement - 10 3/4" at 1111' circulated  
with 465 sax cement - 7" at 3376' with 265 sax cement - 4 1/2" at  
3390' with 50 sax cement - perforated at 3373'.

Crushed rock to 3370', set 5 sax cement with dump bailer, pulled  
3020' 4 1/2" and 2140' 7", filled with mud to 300', set rock and  
25 sax cement, mud to 30', set rock and 10 sax cement to bottom  
cellar.

RECEIVED  
STATE CORPORATION COMMISSION

*Edna Peete*  
District Conservation Agent

Date 3-5-54

**PLUGGING**  
MAR 9 - 1954  
03-09-54  
FILE SEC 21 T 11 R 17  
CONSERVATION DIVISION  
Wichita, Kansas  
PAGE 17 LINE 9