

16 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1964
11-30-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Co
Complete Address: 1132 Wichita Plaza Wichita, Kans
Lease Name Hadley Well No. 2
Location CSL SW NW Sec. 21 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3370
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 5PM Day 28 Month 11 Year 64

The Above well was plugged as follows:

10 3/4" 252' circulated with cement - 7" 3368' with 100 sax cement -
& squeezed in Dakota section at 800' with cement. Tubing lost in hole
top of tubing at 2837' - top of rods left in hole 2600'.

Started 330' of 7" casing - pumped hole full heavy gel mud through 7"
at 330' (26 sax Gel mud), displaced 50 sax Cement through 7" at 300',
heavy mud to 150', displaced 50 sax cement through 7" at 150', heavy
mud to 25' 0 capped with 20 sax cement.

Mudding and cementing by Southwest Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/1/64
INV. NO. 242-W

Signed: [Signature]
Well Plugging Supervisor