

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

JAN 23 1975  
01-23-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thornton E. Anderson

Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202

Lease Name Rumsey Well No. 13

Location NE NE NW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3380'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10:15 A Day 22 Month 1 Year 1975

The above well was plugged as follows:

- Total Depth 3380' 16" csg 116' cwc 150 sx 10 3/4 csg 1090' cwc 350 sx.
- 7" csg 3370' cw 200 sx cem.
- Set 7" wood plug 3350' -poured 50' sd -dumped 6 sx cem W/dump bailer. (3350-3270)
- Cutoff & recovered 2535' of 7" csg.
- Filled 10 3/4 csg W/mud to 415' -set rock & sand bridge (415-400)
- Filled with RM cem from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Les F. Moseley  
Well Plugging Supervisor

INVOICED

DATE 1/30/75  
INV. NO. 716-W