

15-051-03394-0000

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1960  
08-05-60  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: NW NE SE Sec. 23 Twp. 11 Rge. 17 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3424

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 11  
Operator's Full Name: Cities Service Co  
Complete Address: Cities Service Bldg Bartlesville, Okla  
Plugging Contractor: C. E. Shull  
Address: Great Bend, Kans License No. 8  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 2 Month 8 Year 60

The above well was plugged as follows:

8 5/8" 988' circulated with cement - 5 1/2" 3418' with 100 sax behind and squeezed at 998' with 200 sax cement.

Pulled 560' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550' (30 sax Halco Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: *Edson Letty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor *JMB*

Remarks:

INVOICED  
DATE 8-5-60  
INV. NO. 1767.00