

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 1 1963
03-01-63
CONSERVATION DIVISION
Wichita, Kansas SSIO

Operator's Full Name Kerr-McGee Oil Industries, Inc. ANB KCC

Complete Address: Kerr-McGee Bldg Oklahoma City, Okla W

Lease Name Rumsey Well No. 1

Location SW SW SW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3928

Abandoned Oil Well NA Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Cementing Co

Address: Hays, Kans License No.

Operation Completed: Hour 6PM Day 26 Month 2 Year 63

The Above well was plugged as follows:

~~15" 21' - 10 3/4" 1114' circulated with 450 sax cement - 7" 3378' with 250 sax cement - 5 1/2" liner 235' set at 3596' with 150 sax cement. String of 3" tubing with packer lost in hole, top of tubing at 829' - tried to fish tubing by pulling 7" - 7" parted at 719' - tried to fish tubing and mill over - this failed. Pumped hole full of heavy mud - circulated through 2 1/2" tubing - 50 sax gel - displaced 30 sax cement through 2 1/2" tubing at 450' - heavy mud to 190' - displaced 30 sax cement through 2 1/2" tubing at 190', heavy mud to 40' set 15 sax cement to bottom cellar.~~

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/1/63

INV. NO. 6659-W

Signed: [Signature]
Well Plugging Supervisor