

15-051-03384-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Company.

Complete Address Box 553 Russell, Kansas 67665

Lease Name Rumsey "A" Well No. 1

Location NW NW SW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3374'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 675224 License No. 436

Operation Completed: Hour 7:30 P Day 31 Month 5 Year 1972

The above well was plugged as follows:

Total Depth 3374' 10 3/4 csg set at 1100' cwc: 500 sk.

7" csg set at 3366' cw 200 sk cmt.

7" csg squeezed at 2625' W/400 sk cmt.

Filled 7" csg W/sd! (3350-3374) Dumped 6 sk cmt W/dump bailer. (3315-3350)

Cutoff and recovered 1600' of 7" csg.

Pumped down 10 3/4 csg wirh 25 sk gel \$ water W/300 lbs hulls, released 10 3/4 plug  
and pumped 12 1/2 sk cmt. (Halib.-light)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey  
Well Plugging Supervisor

INVOICED

DATE 6-6-72

INV. NO. 5810-W