

15-051-19363-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1962
03-30-62
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NW NW NW Sec. 23 Twp. 11 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3413

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 1

Operator's Full Name: Great Bend Pipe & Supply Co

Complete Address: Drawer (B) Great Bend, Kansas

Plugging Contractor: R & D Casing Pulling Co

Address: Hutchinson, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 16 Month 3 Year 62

The above well was plugged as follows:

15" 219' circulated with cement - 10" 1130' with 400 sax cement - 7"

3409' with 125 sax cement.

Filled with sand to 3390', set 5 sax cement with dump bailer - pulled

2565' 7" to 550', circulated hole with heavy mud through 7" (25 sax Gal)

displaced 25 sax cement through 7" at 550', heavy mud to 180', displaced

25 sax cement through 7" at 180', heavy mud to 30', cement 30' to bottom

cellar.

Mudding and cementing by R&D Company pump truck.

Signed: Edson Perry
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 3/30/62
INV. NO. 4918-W