

15-051-03401-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 149-17

LOCATION SW NW SW

SEC. 23 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Rumsey

Operator E. H. Riggs Address 408 Rule Bldg Wichita,

Field \_\_\_\_\_ County Ellis

Total Depth 3365 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

15" at 60' circulated with cement - 10 3/4" at 1100' circulated  
with cement - 7' 3361' with 125 sax cement.

Sand to 3350', set 5 sax cement with dump bailer, pulled approx  
2500' of 7" - filled hole with heavy chunk mud to 450', set rock  
and 30 sax cement, - at 450' - heavy chunk mud to 30', set rock and  
10 sax cement to 0'.

District Conservation Agent

Date 4-16-57

RECEIVED  
STATE CORPORATION COMMISSION

APR 19 1957  
04-19-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 23 T. 11 R. 17W  
BOOK PAGE 149 LINE 17