

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
JAN 16 1975
01-16-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thornton E. Anderson

Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202

Lease Name Rumsey Well No. 2

Location SW NW NW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3444'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Elainwood, Kansas 67526 License No. 462

Operation Completed: Hour 2:30 P Day 14 Month 1 Year 1975

The above well was plugged as follows:

- Total Depth 3444' 16" csg set at 196' cwc 125 sk 10 3/4 csg set 1116' cwc 400 sk.
- 7" csg set at 3394' cw 125 sk cmt.
- Set 7" wood plug at 3350' -dumped 6' sk cmt W/dump bailer. (3350-3320)
- Cutoff & recovered 51 jts A/1530' of 7" csg.
- Filled 10 3/4 csg with mud to 415' -set rock & sand bridge (415-400)
- Filled with RM cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/17/75
INV. NO. 658-W

Signed: Leo J. Massey
Well Plugging Supervisor