

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Rumsey "A" Well No. 2

Location NE NW SW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3481'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:30 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3481' 10 3/4" csg set at 1098' cwc 500 sk.

7" csg set at 3365' cw 150 sk cmt.

5" liner set (3321-3481) FBTD 3401 and perf. (3384)

Filled 5 1/2" csg W/sd & cmt (3359-3401)

Cutoff and recovered 1409' of 7" csg.

Pumped down 10 3/4" csg with 23' sk gel & water, released plug and pumped 100 lbs

hulls and 125 sk cmt. (35-65) W/8% total gel. PSI 350

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

INVOICED

DATE 1-10-72

INV. NO. 4899-11