

R

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 136-35 County: Ellis

Location: NW NE SW Sec. 23 Twp. 11 Rge. 17 (E) - (W)

Name of Field: \_\_\_\_\_ Total Depth: 3373

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 3

Operator's Full Name: Cities Service Oil Co

Complete Address: Box 553 Russell, Kans

Plugging Contractor: C. E. Shull

Address: Great Bend, Kans License No. 8

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No \_\_\_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

RECEIVED  
STATE CORP. COM.  
FEB 4 1959  
02-04-59

Operation Completed: Hour 6PM Day 28 Month 1 Year 59

The above well was plugged as follows:

15" at 114' circulated with cement - 10 3/4" 1095' circulated with  
500 sax cement - 7" 3365' with 150 sax cement.

Filled with sand to 3350', set 5 sax cement with dump bailer, pulled  
2300' 7" - filled hole with heavy pit mud to 400', set rock and 30  
sax cement, heavy pit mud to 180', set rock and 30 sax cement, heav y  
pit mud to 25', set rock and 10 sax cement to 0'.

Signed: J. Lewis Brock  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 23 T. 11 R. 17W  
BOOK PAGE 136 LINE 35