

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 13-3 County: Ellis

Location: SW NE SW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3395 3466 ANBYCC

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 3

Operator's Full Name: E. H. Riggs

Complete Address: 408 Rule Bldg Wichita, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 26 Month 2 Year 59

The above well was plugged as follows:

10 3/4" 1115' circulated with cement - 7" 3386' with 100 sax cement,

5 1/2" at 3386' with 50 sax cement.. Sand to 3370', set 4 sax cement.

Pulled 2200' 5 1/2" and pulled 1700' of 7" to 500', circulated hole

with heavy mud through 7" (Gel), displaced 25 sax cement through

7" at 500', heavy mud to 150', set 20 sax cement, heavy mud to 30',

set rock and 10 sax cement to bottom cellar.

Mudding and cementing by Forbes Co. pump truck.

Signed: *Edson Petty*
Conservation Division Agent

Reviewed: *J Lewis Brock*
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1959 PLUGGING
03-05-59
CONSERVATION DIVISION
Wichita, Kan
FILED SEC. 23 T. 11 R. 17W
BOOK PAGE 13 LINE 3