

*R*

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 146-10 County: Ellis

Location: NW SW NW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3422

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 3

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: E & L Pipe Pulling Co

Address: Great Bend, Kans License No. 249

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 2 Month 12 Year 58

The above well was plugged as follows:

10" at 1110' circulated with cement - 13" 198' circulated with cement,  
7" 3397' with 125 sax cement behind.

Filled with sand to 3410', set 5 sax cement with dump bailer, pulled  
2785' 7" to 550', circulated hole with heavy mud through 7" at 550',  
displaced 20 sax cement through 7" at 550', heavy mud to 200', displaced  
20 sax cement through 7" at 200', heavy mud to 35', set rock and 10 sax  
cement to bottom cellar.

Mudding and cementing by E & L Pump truck.

Signed: *Edwin Lee*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 231 TWP. 11 R. 17W  
BOOK PAGE 146 LINE 10

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 - 1958  
12-9-58  
CONSERVATION DIVISION  
Wichita, Kansas