

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 14-31 County: Ellis

Location: SE NE SW Sec. 23 Twp. 11 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3477

I have this date completed supervision of plugging of:

Lease Name: Rumsey Well No. 4

Operator's Full Name: E. H. Riggs

Complete Address: 111 Union Natl Wichita, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 2 Month 3 Year 59

The above well was plugged as follows:

15" at 55' circulated with cement - 10 3/4" 1090' circulated
with cement - 7" 3474' with 150 sax cement. P.B. to 3200', perforations
and 3062'.

Filled with sand to 3050', set 5 sax cement with dump bailer, pulled
2450' 7" to 550', circulated hole with heavy mud (26 sax Gel),
displaced 25 sax cement through 7" at 550', heavy mud to 150',
displaced 25 sax cement through 7" at 150', heavy mud to 30', set
rock and 10 sax cement to bottom cellar.

Mudding and cementing by Forbes Co pump truck.

Signed: _____
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION
03-07-59
MAR 7 1959

PLUGGING
FILE SEC 23 T. 11 R. 17
BOOK PAGE 14 LINE 31

CONSERVATION DIVISION