

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JAN 16 1975
01-16-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thornton E. Anderson

Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas

Lease Name Rumsey Well No. 4

Location NE NW NW Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3379'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 2 P Day 14 Month 1 Year 1975

The above well was plugged as follows:

Total Depth 3379' 16" csg 200' cwc 125 sx. 10 3/4" csg 1084' cwc 410 sx.

7" csg set 3360' cw 125 sx cem.

Set 7" wood plug at 3315' -poured 50' sd -dumped 6 sk cmt W/dump bailer. (3315-3236)

Cutoff & recovered 2594' of 7" csg.

Filled 7" csg W/mud to 515' -set rock & sand bridge (415-400)

Filled with readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1/17/75

INV. NO. 659-W