

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1975
03-07-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thornton E. Anderson

Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas 67202

Lease Name J.L. Rumsey ABRCC Well No. 30

Location SE NE NE Sec. 23 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3400'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 3 P Day 66 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3400' 13" csg 132' cwc 125 sx. 8 5/8 csg 1098' cwc 325 sx.

4 1/2 csg 3390' cw 100 sx. cem. PFS (3389')

Filled 4 1/2 csg W/sd (3400-3375) dumped 4 sk cem W/dump bailer. (3375-3345)

Cutoff & recovered 2160' of 4 1/2 csg.

Drlg. Mud to 450' -set rock & sand bridge (450-425)

Filled with readymix cement from 425' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 3/11/75

INV. NO. 954-W