

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5318 EXPIRATION DATE 6-30-83

OPERATOR Energy Reserves Group, Inc. API NO. 15-051-23,411-00-00

ADDRESS 925 Patton Road COUNTY Ellis

Great Bend, Kansas 67530 FIELD Marvin

** CONTACT PERSON Jim W. Sullivan PROD. FORMATION None

PHONE 316-792-2756

PURCHASER NA LEASE Braun 'D'

ADDRESS WELL NO. 1

WELL LOCATION SW SE NE

DRILLING Slawson Drilling Company, Inc. 2310 Ft. from north Line and

CONTRACTOR 200 Douglas Building 990 Ft. from east Line of

ADDRESS Wichita, Kansas 67202 the NE (Qtr.) SEC 22 TWP 13 RGE 18W.

PLUGGING Halliburton

CONTRACTOR ADDRESS 1100 E. 8th St.

Hays, KS 67601

TOTAL DEPTH 3715 PBD 3600

SPUD DATE 5/16/83 DATE COMPLETED 5-24-83

ELEV: GR 2113 DF 2116 KB 2119

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE NA

Amount of surface pipe set and cemented 550 DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Jim W. Sullivan, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.



Jim W. Sullivan (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 20th day of June, 1983.

Ronald C. Rowe (NOTARY PUBLIC)

MY COMMISSION EXPIRES: My Appointment Expires Sept. 9, 1983

** The person who can be reached by phone regarding any questions concerning this information.

RECEIVED STATE CORPORATION COMMISSION JUN 24 1983 CONSERVATION DIVISION Wichita, Kansas

FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
DRILLERS LOG				LOG TOPS	
0' to 755'	Sand & Shale			Zero @ KB	+2119
755' to 1370'	Shale & Sand			GL	+2113
1370' to 1376'	Shale				
1376' to 1421'	Anhydrite			Anhydrite	1372 +747
1421' to 2480'	Shale			Topeka	3111 -992
2480' to 3050'	Lime & Shale			Heebner	3356 -1237
3050' to 3175'	Shale & Lime			Toronto	3380 -1261
3175' to 3340'	Lime & Shale			Lansing	3410 -1291
3340' to 3400'	Shale & Lime			Stark Shale	3595 -1476
3400' to 3444'	Lime & Shale			Base KC	3640 -1521
3444' to 3715'	Lime			Arbuckle	3661 -1542
RTD 3715'				LTD	3714
				RTD	3715
		3354	3444	LOGS RUN	
DST #1 Toronto & L-KC 'B' zn 30-60-60-120 Rec. 210' SOWCM IHP 1,886 IFP 81-92 ISIP 1,021 FFP 138-161 FSIP 986 FHP 1,852 BHT = 112° F				Welex Gamma-Guard Sidewall-Neutron	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~(Used)~~ XXXXXX

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf. Casing	12 1/4"	8-5/8"	20#	550	Halliburton	350	50/50 Poz 2% gel 3%CC 50/50 Poz 3%CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Dry Hole		
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Perforations