

Elev. 2277

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

**WELL PLUGGING APPLICATION FORM**

(File One Copy)

15-051-02837-0000

API NUMBER 11-8-52 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Brook Oil & Gas Corp. OPERATORS LICENSE NO. 4694 1092

ADDRESS Dean Ellner Bldg. 25th. & Vine St.  
Suite 2 Hays, Kans. 67601 PHONE # (913) 628-1909

LEASE (FARM) G.E. Riedel WELL NO. 4 WELL LOCATION SW SW SE COUNTY Ellis

SEC. 31 TWP. 13S RGE. 19 (E) or (W) TOTAL DEPTH 3912 PLUG BACK TD 3912

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 10 3/4 SET AT 241 CEMENTED WITH 250 SACKS

CASING SIZE 7" SET AT 390.5 CEMENTED WITH 17.5 SACKS

PERFORATED AT O.H. 390.5-3912

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL DV at 1575' w/ 120 BBL Kenpack

Run slick line and check TD at 3912'. Tie onto 7" CSG. and pump 550 SKS.

65-35 Poz-Mix 8% Gel. Pressure 7" to 500" and S.I. (over)  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain) Do not have

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8-10-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ted Luebbers PHONE # (913) 628-1909

ADDRESS 25th. & Vine St. Dean Ellner Bldg. Suite 2 Hays, Ks. 67601

PLUGGING CONTRACTOR Halliburton LICENSE NO. 5187 RECEIVED STATE CORPORATION COMMISSION

ADDRESS P.O. Box 428 Hays, Ks. 67601 PHONE # (913) 625-343111 8-1992

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Ted Luebbers CONSERVATION DIVISION  
(Operator or Agent) Wichita, Kansas

DATE: 7-8-92

(4)

Tie onto  $10\frac{3}{4}$ " x 7" Annulus and pump cement until it holds  
500". S.I.

Note: Squeezed CSG. Leak at 941' w/150 SKS. Squeezed at  
1604' and 1290'.

Note: Anhydrite and Dakota to be perforated Run tbg. to cement

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 9, 1992

15051-02887-0000  
G E Riedel 4  
SW SW SE  
Sec. 31-13-19W  
Ellis County

Brock Oil & Gas Corp  
25th & Vine St  
Dean Ellner Bldg 2  
Hays KS 67601

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200