

15-051-20549-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil and Clinton Oil 12-29-1969
Complete Address 1425 Wichita Plaza Wichita, Kansas
Lease Name Slaughter Well No. 1
Location NE NE NE Sec. 8 Twp. 13 Rge. (E) (W) 19
County Ellis Total Depth 3892
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1:45P Day 28 Month 12 Year 1969

The above well was plugged as follows:

RTD 3892' 8 5/8 csg set at 216' cwc 165 sk. Cmt. Mat. 50-50 poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray
Well Plugging Supervisor

DATE 12-29-69

INV. NO. 1160-W