

15-051-00154-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

[Handwritten signature]

FILE NO. 128-53

LOCATION SW SW SW

SEC. 13 TWP. 13 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Gerken _____

Operator Braden Drg Co Address 802 Union Natl Bk Bldg

Field _____ County Ellis

Total Depth 3900 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. 1

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 231' circulated with cement - 5 1/2" at 3899'

with 75 sax cement behind - perforations at 3846'

Filled with sand to 3830', set 4 sax cement with dump bailer,

Pulled 3400' 5 1/2", filled with mud to 230', set rock bridge

and 15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

PLUGGING
FILE SEC 13 T 13 R 20W
BOOK PAGE 128 LINE 33

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1953
09-30-1953
CONSERVATION DIVISION
Wichita, Kansas

[Handwritten signature]
District Conservation Agent
Date 9-26-53