

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22651-00-00 ✓ h

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Graham-Michaelis Corporation

Complete Address 211 N. Broadway, Box 247, Wichita, Ks. 67202

Lease Name Kraus Well No. #1-13

Location 110' So. of NE/NE/NE Sec. 13 Twp. 13 Rge. 20 (East) (West)

County Ellis Total Depth 3790'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Revin Drilling, Inc.

Address Box 88, Russell, Ks. 67665 License No. _____

Operation Completed: Hour: 2:00AM. Day: 22nd Month: Oct. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8"-338' s.p. cuc. w/220 sacks common-2% Gel-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement.

2nd plug @ 330' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
10-26-1981
OCT 26 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 11-19-81

8352-W