

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051- 21312 CONSERVATION DIVISION
Wichita, Kansas (this well)

Operator's Full Name R. P. Nixon Operations

Complete Address Box 589, Russell, Kansas 67665

Lease Name M. Braun Well No. 3

Location NW SW NE Sec. 22 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3700'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10 A Day 23 Month 11 Year 1977

The above well was plugged as follows:

Total Depth 3700' 8 5/8 csg set 590' cwc 340 sk.

4 1/2 csg set 3684' cw 125 sx. PFS (3288'-3280')

Set 4 1/2 wood plug at 3315' - fill with sand (3315'-3250')

Dump 3 sk cem with dump bailer. (3250'-3220') Cutoff & recovered 3015' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water - followed
with 70 sk 50-50 poz 2% -displaced with 8 sk gel & water -capped with 30 sk
50-50 poz 2% & shutin. MPP 500 lbs. SIP 150 lbs

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 11-29-77
INV. NO. 6265-U