

KANSAS

Form CP-3
Rev. 6-4-68

48
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Betorma Oil Company 15-051-70695-D0-00

Complete Address 603 Union Center Wichita, Kansas

Lease Name Stackhouse Well No. 1

Location NW SE SE Sec. 22 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert - Jones Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 P Day 28 Month 11 Year 1970

The above well was plugged as follows:

RTD 3680' 8 5/8 csg set at 569' cwc 220' Cmt. Mat. 50-50 pOz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 40 sk
cmt thru drill pipe. Heavy mud to 400' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/1/70
INV. NO. 2962-U

Signed: Leo F. Massey
Well Plugging Supervisor