

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-05-21,911-00-00

245 North Water
Wichita, KS 67202

Operator's Full Name J. B. COLLINS

Complete Address 1007 CODY - SUITE A - HAYS, KS. 67601

Lease Name GROSS Well No. # 1

Location APP. NE-SE-NW Sec. 22 Twp. 13 Rge. 18 (~~East~~) (West)

County ELLIS Total Depth 3659 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated CONVERTED TO WATER WELL.

Plugging Contractor ALLIED CEMENTING COMPANY, INC.

Address BOX 31-332 WICHITA, RUSSELL, KS. License No. _____

Operation Completed: Hour: 4:45 P.M. Day: 5th Month: DEC. Year: 19 80

The above well was plugged as follows:

8 5/8" 1360 FE SP. CMC. w/ 250 ST 60/40 POZMIX - 2% GEL. - 3% CH.-CL.

5 1/2" SET AT. 3659 FE w/ 100 ST CMT. - PERF'S 3631 FE to 3240 FE

BOTTOM SANDED TO 3300 FE AND w/ 5 ST CMT. SHOT PIPE @ 2525 FE. 2525 FE

ORDERED - 100 ST 50/50 POZMIX 6% GEL. -> 8 ST GEL. -> 2 ST HULL'S AND 8 5/8" PLUG.

PUMPED IN WITH PUMP TRUCK.

PUMPED IN 8 5/8" - 1 ST HULL'S -> 8 ST GEL. - 1 ST HULL'S -> 100 ST CMT.

RELEASED PLUG. AND DISPLACED PLUG. AT 600 FE MAX. PRESSURE 1600 ^{LBS}

SHOT IN PRESSURE. 800 ^{LBS} WELL WILL BE UTILIZED AS WATER WELL.

BY OWNER.

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-12-80

INV. NO. 3871-W

Signed: [Signature]
Conservation Division Agent

DEC 10 1980
CONSERVATION DIVISION
Wichita, Kansas
12-10-80