

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 20, 520-00-00 (of this well)

Operator's Full Name Energy Reserves Group, Inc.

Complete Address 1022 Hoover, Great Bend, Ks. 67530

Lease Name Marvin Braun Well No. 3

Location NW NE NW Sec. 22 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3638'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. tools by Sun Cementing Co.

Address Hays, Ks. 67601 License No.

Operation Completed: Hour 5:15 P Day 16 Month 3 Year 1979

The above well was plugged as follows:

Total Depth 3638' 8 5/8 csg set 565' cwc 325 sk.

5 1/2 csg set 3638' cw 175 sk cem.

5 1/2 csg BP set 2950'. Sq. hole 1065'-1069' ^{1 1/2" w/ 300 ft.} Lost hole when drilling out cement-bit
went outside oil string. (5 1/2 csg)

Pumped down annulus with A/500 bbl rotary mud. Followed with 25 sk cem.

Pumped down 5 1/2 csg with 100 sk cem. FPP 500 lbs.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bud Massey
Well Plugging Supervisor

DATE 3-20-79
INV. NO. 9296-u

15-05120570-00-00
ROTARY DRILLING LOG

Operator: Clinton Oil Company
and Rains & Williamson
Oil Co., Inc.
BRAUN #3-D
NW NE NW Sec. 22-13S-18W
Ellis County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 10-21-69
Completed: 10-31-69
Casing: 8-5/8"/565'/336 sx.
5-1/2"/3637 1/2'/175
sx.

Formations

| | |
|----------------------------|-------|
| Surface Dirt | 26' |
| Post Rock | 30' |
| Shale with Shells and Sand | 596' |
| Shale | 765' |
| Dakota Sand | 1020' |
| Shale | 1260' |
| Shale with Shells | 1342' |
| Anhydrite | 1385' |
| Shale and Shells | 1598' |
| Shale and Red Bed | 1990' |
| Shale with Lime Streaks | 2110' |
| Shale and Lime | 2555' |
| Lime and Shale | 3114' |
| Lime | 3638' |
| Rotary Total Depth | 3638' |

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1978


CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct, to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the
State of Kansas, County of Sedgwick, this 3rd day of November, 1969.


Sherry Gish Notary Public

My Commission Expires:

6-30-71