

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-051-20531-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Harold Mauck Well No. 2#V

Location SW NW NE NW Sec. 22 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3700'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11 A Day 18 Month 9 Year 1971

The above well was plugged as follows:

Total Depth 3700' 8 5/8 csg set at 603' cwc

4 1/2 csg set at 3699' cw 250 sk cmt.

4 1/2 csg PBD 3662' with top perf. (3366')

Set 4 1/2 wood plug at 3300' -poured 20' sd -Dumped 3 sk cmt W/dump bailer. (3250-3300)

Pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls, release plug and

pumped 130 sk 50-50 poz W/4% added gel. Max pres 600 lbs. SI pres 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo L. Massey
Well Plugging Supervisor

INVOICED

DATE 9-22-71

INV. NO. 4353-W