

15-051-03439-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1972
CONSERVATION DIVISION
Wichita, Kansas
02-28-72

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colaham "B" Well No. 7

Location SW NW SW Sec. 25 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3516'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 6:30 P Day 25 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3516' 8 5/8 csg set at 348' cwc 175 sk.

5 1/2 csg set at 3479' cw 100 sk cmt.

5 1/2 csg squeezed (820-851) with 150 sk cmt.

No pipe recovered.

Ram 2" tub. to 3000' -displaced 100 lbs hulls & 25 sk cmt. (2775-3000)

Pulled tub. to 2700' -displaced 25 sk gel & water. (275-2775)

Pulled tub. to 540' -circ. 75 sk cmt to surface. (0-540)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/28/72

INV. NO. 5232-W