

15-051-03435-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1972
06-05-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colahan "B" Well No. 2

Location NE NW NW Sec. 25 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3576'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 5:30 P Day 31 Month 5 Year 1972

The above well was plugged as follows:

Total Depth 3576' 8 5/8 csg set at 1175' cwc300 sk.

5 1/2 csg set at 3570' cw 100 sk cmt.

5 1/2 csg squeezed at 820-851 W/150 sk cmt & 701 W/106 sk cmt.

No pipe recovered.

Ran 100 jts tbg set at 3050' -pumped 25 sk gel & water W/100 lbs hulls, -displaced

25 sk cmt. Pulled tbg to 600' -circ. 55 sk cmt to surface. Pulled remaining 20 jts

tbg. & filled 5 1/2 csg W/5 sk cmt to surface.

Pumped down anulus with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Mearns
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5811-W