

15-051-03434-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
03-06-72

Operator's Full Name Cities Service Oil Company  
Complete Address Box 553 Russell, Kansas 67665  
Lease Name Colaham "B" Well No. 1  
Location SW NW NW Sec. 25 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3600'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas License No. 4365  
Operation Completed: Hour 12:15 P Day 2 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3600' 8 5/8 csg set at 1110' cwc 540 sk.  
5 1/2 csg set at 3555' cw 100 sk cmt.  
Set 5 1/2 wood plug at 3250' -poured 10' sd -Dumped 5 sk cmt. W/dump bailer. (3200-3250)  
Cutoff and recovered 1147' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug  
and pumped 105 sk Halib-Light cmt by HOWCO. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 3-6-72

INV. NO. 5292-12