

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 - 22,826 ~~0000~~

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Cities Service Co.

Complete Address 800 Sutton Place, Bldg. 209 E. William, Wichita, Ks. 67202

Lease Name Colahan "B" Well No. 25

Location SE SE SE Sec. 25 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3480'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Woodman Innitti Drilling Co.

Address 1008 Duglas Bldg. 104 S. Broadway, Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 8:00 PM Day: 2 Month: March Year: 19 82

Plugging Operations attended by Agent?: All XXX Part _____ None _____

The above well was plugged as follows:

8 5/8" - 390' S.P. cuc. W/ 300 sacks common-2% Gel-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug
Spot W/ drill stem W/ heavy mud between all plugs.

1st plug @ 750' W/ 70 sacks cement

2nd plug @ 310' W/ 40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 390' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 3-10-82
INV. NO. 9610-W

RECEIVED
STATE CORPORATION COMMISSION
MAR - 8 1982
03-08-82
CONSERVATION DIVISION
Wichita Kansas