

P
KANSAS
STATE CORPORATION COMMISSION
15-051-05125-00-00
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE SE NE Sec. 31 Twp. 13 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3923

I have this date completed supervision of plugging of:

Lease Name: Riedel Well No. 1

Operator's Full Name: A. F. Schmidt

Complete Address: Box 662 Russell, Kans

Plugging Contractor: R & D Casing Pulling

Address: Ellinwood, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 6 Month 11 Year 59

The above well was plugged as follows:

8 5/8" at 260' circulated with cement - 5 1/2" 3920' with 100 sax cement.

Filled with sand to 3900', set 4 sax cement with dump bailer, pulled

3215' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600'

(20 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to

200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Pump truck.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 1/13/60
INV. NO. 425-W