

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location; SW SW NW Sec. 31 Twp. 13 Rge. (E) (W) 19

Name of Field: \_\_\_\_\_ Total Depth: 3992

I have this date completed supervision of plugging of:

Lease Name: Reidel Well No. B-1 SWD

Operator's Full Name: Brunson - Spines

Complete Address: 302 Union Center Wichita, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 19 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 210' circulated with cement. 5 1/2" 3918' with 110 sax cement - DV  
tool 1542' circulated with black magic - 5 1/2" eaten into at 840'

Tried to mill hole out with rotary - lost hole at 1276' - pulled 840' 8 5/8",  
pumped hole full heavy mud ( 35 sax Gel), pumped cementing plug, followed by  
200 sax cement.

Mudding and cementing by Halliburton Co. 300# pump pressure

Signed: *Eason Petty*  
Conservation Division Agent

Reviewed: *Harold Hallis*  
Field Supervisor

Remarks:

**INVOICED**  
DATE 1/22/62  
INV. NO. 4344-W

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 22 1961  
12-22-61  
CONSERVATION DIVISION  
Wichita, Kansas