



15-067-20841-0000

OXY USA INC.

Box 26100, Oklahoma City, OK 73126-0100  
Telephone 405 749-2000

September 12, 1990

Mr. Dave Williams  
Kansas State Corporation Commission  
Conservation Division  
200 Colorado Derby Building  
Wichita, Kansas 67202

RE: Lease Name Changes  
Spikes A #3  
Spikes B #2  
Sec. 19-28S-36W  
Grant County, Kansas

Dear Mr. Williams:

In accordance with your request for information leading to the naming convention of the referenced wells, I have researched our well files and determined that the attached forms ACO-1 and ACO-2 duly reflect the proper nomenclature which is in agreement with the API numbers issued to the Intentions to Drill.

As indicated in our telephone conversation, each of these wells has undergone three name changes due to different reclassifications based on oil and gas production. The chronology in which the wells were drilled also compounded the problem. Therefore, we suggest that the interim reports that are presently on your files be disregarded and final determination of the well names be based on these two records.

Please advise if additional information is required.

Sincerely yours,

Raymond Hui  
Mid-Continent Region

Attachments

SEP 13 1990

CONSERVATION DIVISION  
Wichita, Kansas

15-067-20841-0880

20,769  
Intent: SPIKES A #3  
ACO-1: SPIKES B #1  
(Formerly SPIKES A #3)  
ACO-2 SPIKES A #3

OXY USA, INC. OKLAHOMA CITY, OK 73112		19-28-36W 660'FSL & 1500'FEL SE/4	
#1 SPIKES "B"		API 15-067-20769	
site: 1/4 N & 3-1/2 E OF ULYSSES, KS		city: GRANT	
contr: EXETER DRILLING #13		field: WC (4-1/4 SW OF DAVATZ)	
geol: TOM TINNEY			
fr date: 03/23/88	spd date: 06/09/88	drig comp: 06/21/88	card issued: 10/26/88
last revised: 10/26/88			
ELV: 3098 KB LOG	IP status:		
lops.....depth/datum	OIL: F-160.55 BO & 55.5 BWPD & 688 MCFGPD MRW		
WINF.....2564-1534	5302-5310		
CO GR.....2804-1294	ST LOUIS.....5660-2562		
TOP.....3536-438	LTD.....6098-3000		
HEEB.....3933-835	RTD.....6100-3002		
TOR.....3957-859	NOTE: CORRECTION: 4/20/88 - ORIGINALLY FIRST		
LANS.....4034-936	REPORTED AS CITIES SERVICE OIL & GAS CORP AS		
MARM.....4650-1552	OPERATOR: 4/27/88 - WAS 1250'FSL & 4030'FEL SEC		
CHER.....4826-1728	9/14/88 - WAS #3 SPIKES "A"		
MRW.....5228-2128	CSG: 20" COND AT 70, 8-5/8" 1821 / 650 SX 5-1/2		
MRW SD UPR.....5300-2202	6098 / 905 SX, DV TOOL AT 3117 / 735 SX		
CHEST.....5408-2310			
CHEST SD.....5528-2430			
STE GEN.....5576-2478			
COPYRIGHT 1988 INDEPENDENT OIL & GAS SERVICE, INC. WICHITA, KANSAS			

15-067-20,841  
Intent: SPIKES B #2 <sup>15 correct</sup>  
ACO-1: ~~SPIKES A #3~~  
(Formerly spikes B #2)  
15 spikes B #2

OXY USA, INC. OKLAHOMA CITY, OK 73126-0100		19-28-36W C NW SE	
#3 SPIKES "A"		API 15-067-20841	
site: 1/4 N & 3-1/4 E OF ULYSSES, KS		city: GRANT	
contr: EXETER DRILLING #11		field: RR BEND	
geol: ROBERT VICK			
fr date: 09/28/88	spd date: 11/22/88	drig comp: 12/03/88	card issued: 05/03/89
last revised: 05/03/89			
ELV: 3077 KB LOG	IP status:		
lops.....depth/datum	GAS/OIL, COF 12,379 MCFG & 37 BOPD, NW, MRW		
WINF.....2528+549	5244-5245,		
HEEB.....3900-823	RTD.....5827-2750		
TOR.....3920-843	NOTE: CORRECTION: 11/16/88 - ORIG FR IN C SE NW;		
LANS.....4002-925	4/26/89 - ORIG FR AS #2 SPIKES "B"		
MARM.....4604-1527	CSG: 20" COND AT 45 / 4 YDS, 8-5/8" 1796 / 550 SX,		
CHER.....4782-1705	5-1/2" 5826 / 625 SX, DV TOOL AT 3083 / 880 SX		
MRW.....5190-2113	CORE (1) 5250-5310 (MRW), CUT 60', FULL REC -		
MRW SD UPR.....5238-2161	DETAILS NA		
CHEST.....5360-2283	NO DSTS		
STE GEN.....5562-2485	MICT - CO, PF (MRW) 5241-5245, W / 4 SPF, FLO GSO &		
ST LOUIS.....5622-2545	G, NAT, SET 2-3/8" TBG AT 5245, SI, COF 12,379 MCFG		
PBTD.....5752-2675	& 37 BOPD, NW, IP 2211 MCFG & 37 BOPD, NW 2/18/89		
LTD.....5814-2737			
COPYRIGHT 1988 INDEPENDENT OIL & GAS SERVICE, INC. WICHITA, KANSAS			