

4-29 4-041896

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-03444-0090

E2 NE NE /4 SEC. 25 , 11 S, 17 W
660 feet from N section line
330 feet from E section line

Operator license# 5447

Lease: Colahan "B" Well # 12

Operator: OXY USA, Inc.

County: Ellis 110.89

Address: P.O. Box 300
Tulsa, OK 74102-0300

Well total depth 3412 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 1015 feet
w/ 300 sxs.cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 29 Month: April Year 1997

Plugging proposal received from: Gary Wagner

Company: OXY USA, Inc. Phone: _____

Were: 5 1/2" casing set at 3335' w/125 sxs cement. Anhy. at 1000'. W.L.M. at 3335'.
Squeeze at 750' w/75 sxs cement - circulate to surface.
Ordered 395 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls - 10 sxs gel

RECEIVED
KANSAS CORP COMM
MAY 22 A 12:58
4-22-97

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:45 A.M., Day: 29, Month: April, Year: 1997

Actual plugging report: 5 1/2" casing. Squeezed down casing with 25 sxs cement plus 300# hulls, followed with 10 sxs gel spacer, followed with 370 sxs cement with 200# hulls. S.I.P. 50#.

Remarks: Checked cement on May 1, 1997 - OK. Filled to surface with 95 sxs cement.

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____ , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____ , CASING . Elevation: _____ G.L. _____

I did[] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE 5-22-97

INV. NO. 48166

4-29