

4-041944

12-1

OSI-03445-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-1947

W2 SW SW /4 SEC. 25, 11 S, 17 W  
660 feet from S section line  
4950 feet from E section line

Operator license# 5447

Lease: Colahan "B" Well # 16

Operator: OXY USA, Inc.

County: Ellis 116.45

Address: P.O. Box D  
Plainville, Kansas 67663

Well total depth 3583 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 1140 Feet  
W/400 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools License# 5447

Address:

Company to plug at: Hour: 9:00 A.M. Day: 1 Month: December Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 785-434-7681

Were: 5 1/2" casing set at 3550' w/150 sxs cement. O.H. at 3550' - 3564'.  
Ordered 450 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
Anhy. At 1150' - Dakota at 760' - W.L.M. 1476'.

12-17-97

RECEIVED  
KANSAS CORP COM  
DEC 17 12:30

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 3:00 P.M., Day: 1, Month: December, Year: 1997

Actual plugging report: R.I.H. with tubing to 1850'. Spotted 150 sxs with 500# hulls.  
Pulled to 1400' - spotted 75 sxs cement to circulate cement at surface. P.O.O.H. with tubing.  
Squeezed casing with 35 sxs cement. Max. P.S.I. 300#. R.U. Cementers to 8 5/8" S.P.  
Squeezed casing with 10 sxs cement. Locked-up at 500# P.S.I.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: G.L.

I did[ ] / did not[ X ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE DEC 18 1997  
CIS. NO. 49746  
12-1