

4-28

4-041895

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-03446-0000

NE SE NW /4 SEC. 25, 11 S, 17 W  
1650 feet from N section line  
2310 feet from W section line

Operator license# 5447

Lease: Colahan "B" Well # 17

Operator: OXY USA, Inc.

County: Ellis 114.79

Address: P.O. Box 300  
Tulsa, OK 74102-0300

Well total depth 3532 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 1084 feet  
w/ 500 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 28 Month: April Year 1997

Plugging proposal received from: Gary Wagner

Company: OXY USA, Inc. Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3532' w/150 sxs cement. Perf. at 3104' - 3517'. Anhy. at 1050'. W.L.M. at 3513'. T.O.F. at 1220'.

Ordered 550 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls - 10 sxs gel

RECEIVED  
KANSAS CORP COMM  
MAY 22 12 58

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[ ], Part[  ], None[ ]

Completed: Hour: 3:30 P.M., Day: 28, Month: April, Year: 1997

Rec'd  
5-22-97

Actual plugging report: 5 1/2" casing. Mixed and squeezed 50 sxs cement with 400# hulls, followed with 10 sxs gel, followed with 460 sxs cement w/200# hulls. Max. P.S.I. 100#. S.I.P. 0#. 8 5/8" S.P. Squeezed 40 sxs cement at Max. P.S.I. 500#. S.I.P. 400#.

Remarks: Checked cement on May 1, 1997 - OK.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING  \_\_\_\_\_

Anhy.plug: YES  NO \_\_\_\_\_  
Dakota plug: YES  NO \_\_\_\_\_  
Elevation: \_\_\_\_\_ G.L.

I did[  ] / did not[ ] observe the plugging.

Dennis L. Hamel  
(agent)

**INVOICED**

DATE 5-22-97

INV. NO. 48167

4-28