

6-090454

2-28

Rec'd  
3-13-91

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-24,727 0000  
W/2 NW SE /4 SEC. 25-, 11 S, 17 W  
1980 feet from S section line  
2310 feet from E section line

Operator license# 5447 Lease Colahan "B" well # 27

Operator: OXY USA, Inc. County Ellis

Address: 110 South Main, Suite 800 Well total depth 3575 feet  
Wichita, Kansas 67202 Conductor Pipe:      inch @      feet  
Surface pipe 8 5/8 Inch @ 330 feet

116.18

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Duke Drilling Company License# 5929

Address: Great Bend, Kansas 67530

Company to plug at: Hour: AM Day: 26 Month: February Year: 1991

Plugging proposal received from: Don Sheldon

Company: OXY USA, Inc. phone:     

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3526 feet with 20 sacks Rat hole: 15 sacks  
2nd plug @ 1170 feet " 20 " Mousehole:      sacks  
3rd plug @ 640 feet " 100 "  
4th plug @ 380 feet " 40 "

5th plug @ 40 feet wiper plug & 10 sacks

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 2:30 AM, Day: 28, Month: February, Year: 1991

Actual plugging report: Hole reported plugged as above.  
Order 205sx 60/40 pozmix w/ 6% gel and 2sx celloflake or flowcel.

Remarks: Elevation: 1962 GL, Anhydrite depth: 1152 -      feet

Did      penetrate Arbuckle, cemented by B J Services

I did[      ] / did not[ X ] observe the plugging. Ed Schumacher

**INVOICED**

DATE 3-15-91

INV. NO. 31186

2-28

*File 5*

Ed Schumacher P.I.R.T. III  
(agent)