

4-071009

10-14

216
R

02837.0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-11-8-52

SW SW SE /4 SEC. 31, 13 S, 19 W
330 feet from S section line
2310 feet from E section line

Operator license# 4694

Lease G.E. Riedel well # 4

Operator: Brock Oil & Gas Corporation

County Ellis

Address: 25th & Vine Street
Suite #2
Hays, Kansas 67601

Well total depth 3912 feet ^{127.14}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4Inch @ 241 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Services License# -

Address: East Highway 40 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 14 Month: October Year: 92

Plugging proposal received from: Ted Luebbers

Company: Brock Oil & Gas Corporation Phone: 913-628-1909

Were: 10 3/4" - 241' S.P. cwc. w/250 sx. cement. 7" casing set @ 3905' w/175 sx. cement. D.V. @ 1575' circulated with ken pack. Also cement squeezes at 941' w/150 sx. - @ 1604' w/N.A. - and @ 1290' w/N.A. Perfs open hole 3905' - 3912'. Proposal 600 sx. 65/35 pozmix - 8% gel and 5 sx. hulls. Pump in with pump truck, load both 7" casing and 7" x 10 3/4" casing from top to bottom and shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:15P.M., Day: 14, Month: October, Year: 92

Actual plugging report: Brock Oil Company order 600 sx. 65/35 pozmix - 8% gel. and 5 sx. hulls pumped in with pump truck.

1) Pumped in 7" casing with 15 sx. cement followed with 460 sx. cement with 4 1/2 sx. hulls added. Max. pressure 800 P.S.I. Shut in pressure 450 S.I.P. 2) Pumped 125 sx. cement in 7" x 10 3/4" annulus. Max. pressure 300 P.S.I. Shut in at 150 P.S.I.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by: Halliburton
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

Marion J. Schmidt
(agent)

DATE 11-20-92

INV. NO. 36827

DEC 11 1992