

4-21

4-071040

05383.00.00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051 - 3-5-53

NE SE SW /4 SEC. 31, 13 S, 19 W
2310 feet from S section line
2970 feet from E section line

Operator license# 4694 Lease G.E. Riedel well # 6

Operator: Brock Oil & Gas Corporation County Ellis 127.01

Address: 25th & Vine - Ellner Bldg.#2 Well total depth 3908 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Ted Luebbers Surface pipe 10 3/4 Inch @ 278 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Rapid Well Sevice License#

Address: Russell, Kansas 67665 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: April Year: 93

Plugging proposal received from: Ted Luebbers

Company: Brock Oil & Gas Corporation Phone: 913-628-1909

Were: 10 3/4" - 278' S.P. cwc. w/250 sx. cement. 7" casing set @
3897' w/175 sx. cement. Perf. 3897'. D.V. @ 1569' with Kem Pack.
Proposal 525 sx. 65/35 pozmix - 10% gel. Spot and displace all cement
through tubing. Load 7" casing with cement, also squeeze annulus with
cement. Perf. casing @ 877' - 1520' and 2200'.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 21, Month: April, Year: 93

Actual plugging report: Brock ordered 600 sx. 65/35 pozmix - 10% gel. -
5 sx. hulls. Spotted and displaced all cement through tubing.

- 1) Perferated 7" casing @ 877' - 1520' - 2200' - 3 holes 120'.
- 2) 2 7/8" tubing @ 3750' w/200 sx. cement with 1 1/2 sx. hulls.
- 3) 2 7/8" tubing @ 1980' w/425 sx. cement. 4) 2 7/8" tubing @ 900'
- w/115 sx. cement with 2 1/2 sx. hulls. Cement circulated out of 7"
- casing. 5) 7" x 10 3/4" annulus w/40 sx. cement - 200 P.S.I.
- 6) 7" casing load with 10 sx. cement.

Remarks: Cemented by Allied Cement - Hays, Kansas
Condition of casing(in hole):GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GI

I did X / did not observe the plugging.

Marion Schmidt
DH (agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1993

CONSERVATION DIVISION
Wichita, Kansas

05-12-93

INVOICED
DATE 5-14-93
INV. NO. 37706
4-21