

X

4-110089

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-02,850-0000

NE NE SE /4 SEC. 31, 13 S, 19 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 30606  
Operator: Murfin Drilling Company  
Address: 250 N. Water - #300  
Wichita, Kansas 67202

3/16

Lease: Gus Riedel Well # 10  
County: Ellis 126.26

Well total depth 3885 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 227 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: 312 S. Main - P.O. Box 467 - Chase, Kansas 67524-0209

Company to plug at: Hour: 10:30 A.M. Day: 16 Month: March Year: 2000

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Plug according to KCC Rules & Regulations.  
Ordered 525 sxs 60/40 poxmix - 10% gel - 40 sxs gel - 900# hulls.  
Plug through tubing.  
Perfs at 2150' - 1500' - 200'.

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 2000

Plugging Proposal Received by: Dennis Hamel CONSERVATION DIVISION  
Plugging operations attended by agent? All [ X ], Part [      ], None [      ] Wichita, Kansas

Completed: Hour: 6:00 P.M., Day: 16, Month: March, Year: 2000

Actual plugging report: 10 3/4" S.P. set at 229' w/200 sxs cement. 7" casing at 3868' with 175 sxs cement. Ran tubing to 3627' and pumped 20 sxs gel and 60 sxs cement with 300# hulls. Pulled tubing to 2200' and pumped 200 sxs cement and 300# hulls. Pulled tubing to 1100' and circulated with 215 sxs cement and 300# hulls. Pulled all tubing and squeezed 7" casing with 145 sxs cement to 100# S.I.P. Total of 620 sxs 60/40 poxmix with 10% gel - 20 sxs gel and 900# hulls.

Remarks: Allied Cementing. Werth Tank Service - Water.

Condition of casing(in hole): GOOD      BAD X Anhy.plugin: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING X, CASING     . Elevation: 2245 GL

I did [ X ] / did not [      ] observe the plugging.

Raymond L. Moses  
(agent)

Form CP-2/3

INVOICED  
DATE 4/20/00  
INV. NO. 06/618

R

TEXAS COMPANY

#10 RIEDEL

31-13-19W 35  
NE NE SE

Contr. STICKLE DRILLING ELLIS County

E. 2251 RB 10-31-52 Comp. 12-19-52 IP 452 BOPD  
Comm. PHY POJ

Tops	Depth	Datum
TOP	3215	- 994
HEEB	3497	-1246
LANS	3539	-1288
CONG	3839	-1588
ARB	3867	-1616
TD	3885	-1634

Casing  
10" 227  
7" 3868

DP & CO, SWB 78 B0/11  
HRS:  
ACID 500, 88 B0 & TR  
WTR/5 HRS: 16 1/2 B0  
IRVIN PH & TR WTR/4 HRS.

NORTH POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

RECEIVED  
APR 14 1953  
WICHITA, KANSAS

# ALLIED CEMENTING CO., INC. 3755

Federal Tax I.D.#

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-051-02850-00-00

DATE <u>3-16-00</u>	SEC <u>31</u>	TWP <u>13</u>	RANGE <u>19W</u>	CALLED OUT	ON LOCATION	JOB START <u>11:00 AM</u>	JOB FINISH
LEASE <u>G. Rieder</u>	WELL # <u>10</u>	LOCATION <u>Naya Golf Course Rd</u>	COUNTY <u>Ellis</u>	STATE <u>Ks</u>			
OLD OR NEW (Circle one)			<u>7W 1 1/2 N</u>				

CONTRACTOR <u>Mikes Testing &amp; Salvage</u>	OWNER
TYPE OF JOB <u>plug to abandon</u>	
HOLE SIZE <u>7"</u>	T.D.
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT AMOUNT ORDERED <u>625<sup>60</sup> 10% gel</u>	
<u>9 Hulls 20 gel</u>	
COMMON <u>375</u>	@ <u>6.35</u> <u>2381.25</u>
POZMIX <u>250</u>	@ <u>3.25</u> <u>812.50</u>
GEL <u>63</u>	@ <u>9.50</u> <u>598.50</u>
CHLORIDE	@
<u>Hulls 9</u>	@ <u>15.00</u> <u>135.00</u>
	@
	@
	@
	@
HANDLING	@ <u>1.25</u> <u>656.25</u>
MILEAGE <u>42/sk   mile</u>	<u>225.00</u>
TOTAL <u>4813.00</u>	

EQUIPMENT	
<u>345</u>	<u>Dave</u>
PUMP TRUCK CEMENTER	<u>Maud</u>
#	HELPER
BULK TRUCK	
# <u>254</u>	DRIVER <u>Jason</u>
BULK TRUCK	
# <u>213</u>	DRIVER <u>Jon</u>

REMARKS:  
Raw tubing to 3600 spat 20 gel  
wt 1 Hull allowed up 60 cement  
+ 2 Hull pulled to 2200' spat 200 sk  
+ 3 Hull pulled to 1600'  
Spat 2 1/2' sk + 3 Hull +  
circ cement pulled tubing tied  
on to 7" + mixed 50 sk wait on  
Cement mixed 100 sk + circ up 10% to surface

SERVICE	
DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>450.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>9</u>	@ <u>3.00</u> <u>27.00</u>
PLUG	@
	@
	@
TOTAL <u>477.00</u>	

CHARGE TO: Martin

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT	
	@
	@
	@
	@
	@
TOTAL _____	

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Mike J. Andrews

Maate J Andrews  
 PRINTED NAME

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 1 2000  
 CONSERVATION DIVISION  
 Wichita, Kansas