

4-042042

15-051-02836-0000

API Number: 15- - 4-51

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE SE SE /4 SEC. 31, 13 S, 19 W
990 feet from S section line
330 feet from E Section line

3/29

Operator license# 30606

Lease: Gus Riedel Well # 2

Operator: Murfin Drilling Company

County: Ellis 127.08

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

Well total depth 3910 feet
Conductor Pipe: inch @ feet
Surface Pipe: 10 3/4 Inch 1571 Feet
W/800 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage - Allied Cementing License# -

Address: Chase, Kansas 67524

Company to plug at: Hour: 8:00 A.M. Day: 29 Month: March Year 2000

Plugging proposal received from: Monty

Company: Mike's Testing & Salvage Phone: -

Were: Ordered 525 sxs 60/40 pozmix - 10% gel and 600# hulls.
7" casing set at 3916' w/125 sxs cement. Perf. at 3778' - 3898'.
Plug bottom with sand to 3690' plus 7 sxs cement on sand.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 2:30 P.M. Day: 29, Month: March Year: 2000

Actual plugging report: Shot casing off at 3000'. Pulled casing to 2150' - spotted 300 sxs cement with 600# hulls. Pulled casing to 1500'. Spotted 50 sxs cement. Pulled casing to 900'. Spotted 100 sxs cement. Pulled casing to 150' - circulated cement - 50 sxs at surface. Pulled with cement in cellar.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING CASING Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel (agent)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Form CP-2/3

DATE 4/14/00
INV. NO. 061555

APR 12 2000
04-12-00
CONSERVATION DIVISION
Wichita, Kansas

(Handwritten signature/initials)

ALLIED CEMENTING CO., INC. 3503

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-05102836-00-00

DATE <u>3-29-00</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>8:15am</u>	JOB START <u>8:35am</u>	JOB FINISH <u>12:30pm</u>
LEASE <u>Reidel</u>		WELL # <u>Z</u>		LOCATION <u>Golf Course Rd 7w 1N 1/2N</u>		COUNTY <u>Ellis</u>	STATE <u>Ko</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Michas Testing & Salvage

TYPE OF JOB Re

HOLE SIZE	T.D.
CASING SIZE <u>7"</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER _____

CEMENT

AMOUNT ORDERED 525 60/40 10% gel
400# hulls
used 500 #

COMMON	<u>300</u>	@	<u>6.35</u>	<u>1905.00</u>
POZMIX	<u>200</u>	@	<u>3.25</u>	<u>650.00</u>
GEL	<u>35</u>	@	<u>9.50</u>	<u>332.50</u>
CHLORIDE		@		
<u>Hulls</u>	<u>4</u>	@	<u>15.50</u>	<u>62.00</u>
		@		
		@		
		@		
		@		
HANDLING		@	<u>1.05</u>	<u>55.25</u>
MILEAGE	<u>44/5k</u>	@	<u>1/mile</u>	<u>189.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>MaB</u>
# <u>345</u>	HELPER <u>Don</u>
BULK TRUCK	
# <u>110</u>	DRIVER <u>Jason</u>
BULK TRUCK	
#	DRIVER

TOTAL 3689.75

REMARKS:

RECEIVED
STATE CORPORATION COMMISSION
APR 24 2000
CONSERVATION DIVISION
Wichita, Kansas

SERVICE

300# w/400# hulls @ 2.150

50# @ 15.00

100# @ 9.00

50# @ 1.50 air cement left

cellar full

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>150.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>9</u>	@	<u>3.00</u>
PLUG		@	
		@	
		@	

TOTAL 477.00

CHARGE TO: Murfin

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Monte J Andrews

Monte J Andrews
PRINTED NAME