

4-042038

6-22-52

API Number: 15-051-05,384-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW SE SE /4 SEC. 31, 13 S, 19 W
330 feet from S section line
990 feet from E Section line

126.30

Operator license# 30606

Lease: Gus Riedel Well # 7

Operator: Murfin Drilling Company 3/15

County: Ellis

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

Well total depth 3886 feet

Conductor Pipe: inch @ feet

Surface Pipe: 8 5/8 Inch 667 Feet

W/325 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# -

Address: Chase, Kansas 67524

Company to plug at: Hour: 8:00 A.M. Day: 10 Month: March Year 2000

Plugging proposal received from: Monty

Company: Mike's Testing & Salvage Phone: -

Were: Ordered 300 sxs 60/40 pozmix - 10% gel plus 500# hulls.

5 1/2" casing set at 3872' w/175 sxs cement. Perfs at 3872' - 3886'.

Bridge at 1380'. Perf casing at 1303' - 900' - 200'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 11:00 A.M., Day: 15, Month: March, Year: 2000

Actual plugging report: Run in hole with tubing to 1300'. Spotted 160 sxs cement with 500# hulls to circulate cement at surface. Pulled tubing and squeezed 90 sxs cement down 5 1/2" casing to circulate cement out of annulus. Shut in and pressured up to 500#. Job complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING CASING Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
RECEIVED (agent)
STATE CORPORATION COMMISSION CP-2/3

INVOICED
DATE 4/5/00
INV. NO. 061506

APR 3 2000

CONSERVATION DIVISION
Wichita, Kansas

(R)

ALLIED CEMENTING CO., INC.

2223

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15:057-05384-0000

DATE <u>3-15-00</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>9:45am</u>	JOB FINISH
LEASE <u>Riedel</u>	WELL # <u>7</u>	LOCATION <u>Harp & Griff course Rd</u>			COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>7w IN</u>			

CONTRACTOR Mike Steuting

TYPE OF JOB Ra

HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE <u>2"</u>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER _____

CEMENT

AMOUNT ORDERED 250 60/40 10% gel
500# Sulls

COMMON	<u>150</u>	@	<u>6.35</u>	<u>952.50</u>
POZMIX	<u>100</u>	@	<u>3.25</u>	<u>325.00</u>
GEL	<u>17</u>	@	<u>9.50</u>	<u>161.50</u>
CHLORIDE		@		
<u>Sulls</u>	<u>5</u>	@	<u>15.50</u>	<u>77.50</u>
		@		
		@		
		@		
		@		
		@		
HANDLING		@	<u>1.95</u>	<u>262.50</u>
MILEAGE	<u>24 1/2</u>	/ MILE		<u>100.00</u>
				TOTAL <u>1879.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Mark</u>
# <u>153</u>	HELPER <u>one</u>
BULK TRUCK	
# <u>213</u>	DRIVER <u>Jensen</u>
BULK TRUCK	
#	DRIVER

RECEIVED
STATE CORPORATION COMMISSION SERVICE
APR 24 2000

REMARKS:

Circ cement @ 1200 w/ 1160 @ & 500#
Sulls - pulled tubing tied onto 5 1/2
mixed @ 90 @ w/ & circulated up 8 1/2
slut backside & pressure to 500#

May psi 500# slut in 100#

DEPTH OF JOB			
CONSERVATION DIVISION			
PUMP TRUCK CHARGE			<u>150.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>9</u>	@	<u>3.00</u>
PLUG		@	
		@	
		@	
TOTAL <u>477.00</u>			

CHARGE TO: Munlin

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
	@	

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Monte J Andrews

Monte J Andrews
PRINTED NAME