

4-071041

4-21

02838-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-05/ - 1-31-53

NE NW SE /4 SEC. 31 , 13 S, 19 W  
2310 feet from S section line  
1650 feet from E section line

Operator license# 4694 Lease G.E. Riedel well # 5

Operator: Brock Oil & Gas Corporation County Ellis

Address: 25th & Vine - Ellner Bldg.#2 Well total depth 3913 feet <sup>127.17</sup>  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Ted Luebbers Surface pipe 10 3/4 Inch @ 278 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Rapid Well Sevice License#           

Address: Russell, Kansas 67665 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 21 Month: April Year: 93

Plugging proposal received from: Ted Luebbers

Company: Brock Oil & Gas Corporation Phone: 913-628-1909

Were: 10 3/4" - 278' S.P. cwc. w/250 sx. cement. 7" casing set @  
3905' w/175 sx. cement. Perf. 3905'. Proposal 525 sx. 65/35 pozmix -  
10% gel. - 5 sx. hulls. Spot and displace all cement through tubing.  
Load 7" casing and 7" x 10 3/4" annulus with cement, also perforate  
7" casing @ 873' - 1500' - 2200'. D.V. @ 1549' with 120 bbls. of Kem  
Pack.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 6:00P.M., Day: 21, Month: April, Year: 93

Actual plugging report: Brock ordered 525 sx. 65/35 pozmix - 10% gel. -  
5 sx. hulls. Spotted and displaced all cement through tubing.

Filled both 7" casing and 7" x 10 3/4" annulus with cement.

- 1) Perferated 7" casing @ 873' - 1500' - 2200'. 2) 2 7/8" tubing @
- 3825' w/200 sx. cement with 1 1/2 sx. hulls. 3) 2 7/8" tubing @ 1980'
- w/250 sx. cement with 2 sx. hulls. Cement circulated out of 7" casing.
- 4) Squeezed 7" x 10 3/4" annulus with 50 sx. cement - 300 P.S.I.
- 5) Loaded 7" casing with 30 sx. cement.

Remarks: Cemented by Allied Cement - Hays, Kansas

Condition of casing(in hole):GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO

Plugged through TUBING  , CASING  . Elevation:            GL

I did  / did not  observe the plugging.

**INVOICED**

*Marion Schmidt*  
Agent)

DATE 5-14-93  
INV. NO. 37205  
4-21

RCWD  
05-05-93